LANTRO PHILS., INC.
420 Unit D, F. Legaspi Street Maybunga
Pasig City, Philippines
Tel: 632 621 8619
Fax: 632 470 4740

To: **Pricon Microelectronics, Inc**

QUOTATION

Our Ref	MNMNQU-1802665-Rev0-P
Date	22-Jan-19
Total page	2

Attn: **Ricardo C. Martin III**
Email: rcmartin@pricon.ph
Trunkli **(63)2-843-0870 local 228**

ITEM	PARTICULARS	PART NO.	QTY	U/M	U/P (PHP)	Total Amount (PHP)
RE:	**Pricon @ Canlubang Laguna Supply & Install Panduit Cat6**					
A	**Horizontal Cabling @ (28 nodes)**					
1	Panduit Cat.6 4-pair UTP Cable, Blue	PUC6C004BU	10	box	6,720.00	67,200.00
2	Panduit 24-port Patch Panel, unloaded	CPPL24WBLY	2	ea	1,200.00	2,400.00
3	Panduit Cat.6 Information Outlet, blue	CJ688TPBU	56	ea	324.00	18,144.00
4	Panduit Cat.6 UTP Patch Cord, 1m blue	UTPSP2MBU	28	ea	336.00	9,408.00
5	Panduit Cat.6 UTP Patch Cord, 2m blue	UTPSP3MBU	28	ea	360.00	10,080.00
6	Panduit 1-port Faceplate, off white	CFPE1IW	28	ea	78.00	2,184.00
					Sub-Total for A :	**109,416.00**
B	**Horizontal Roughing-ins**					
1	100mm x 100mm Cable Tray w/ cover & coupling, Flat Black x 8ft	CTRAY-FBL23	25	ea	1,770.00	44,250.00
2	EMT 1" x 10ft w/connector & coupling	LEXTN-IMC-1	120	ea	540.00	64,800.00
3	EMT 3/4" x 10ft w/connector & coupling	LEXTN-IMC-3/4	80	ea	456.00	36,480.00
4	Coupling 1"	LEX-COP-1	80	ea	42.00	3,360.00
5	EMT Elbow 1"	LEX-ELB-1	50	ea	108.00	5,400.00
6	Unistrutt Channel 1⅝ x 1⅝ x 10ft	CAD-UC	10	ea	1,320.00	13,200.00
7	Unistrutt Clamp 1", Caddy	CAD-U1	180	ea	70.80	12,744.00
8	Unistrutt Clamp 3/4", Caddy	CAD-U3/4	120	ea	67.20	8,064.00
9	Angle Bar 1 1/2" x 1 1/2" x 10ft	ABAR3	30	ea	330.00	9,900.00
10	Threaded Round bar 3/8 x 10ft	RNDBAR-3	150	ea	144.00	21,600.00
11	Anchor Bolt 3/8"	ABOLT 3/8"	300	ea	14.40	4,320.00
12	Square Box 4 11/16" x 4 11/16" w/ cover	SQBOX-1	150	ea	108.00	16,200.00
13	Utility Box	UBOX	60	ea	36.00	2,160.00
14	1" Metal flexible x 30m	MFLEX-1	4	reel	1,620.00	6,480.00
15	3/4" Metal flexible x 30m	MFLEX-3/4	2	reel	1,284.00	2,568.00
16	1" Straight Connector	ST CON 1	50	ea	30.00	1,500.00
17	3/4" Straight Connector	ST CON 3/4	20	ea	21.60	432.00
18	Pullbox w/ Cover 400mm X 400mm X 150mm	Locally Fabricated	5	ea	1,428.00	7,140.00
19	Metal Flexible 1" 30mtrs/roll	-	2	reel	1,680.00	3,360.00
20	Metal Flexible 3/4" 30mtrs/roll	-	2	reel	1,380.00	2,760.00
21	Velcro Ties, Black 10m /roll	VELCRO-BLK	2	reel	1,320.00	2,640.00
22	Chipping	-	1	lot	20,000.00	20,000.00
23	Miscellaneous items	-	1	lot	20,000.00	20,000.00
					Sub-Total for B :	**309,358.00**
C	**Racks & Accessories**					
1	WALLMOUNT CABINET H=2FT W=21.5" X D=18" 19" STANDARD OPENING SYSTEMS FRAMING & PANELLING GAUGE# 16 PLEXIGLASS FRONT DOOR W/ PUSHLOCK DETACHABLE SIDE PANELS W/ CAMLOCK FIXED TYPE BACK PANEL W/ 2 PCS. EXHAUST FAN @ THE TOP PANEL W/ VERTICAL POWERSTRIP 4 C.O., 3 PRONG, 220V, 20AMP-FUSE CAPACITY W/ VERTICAL CABLE MANAGER @ THE BACK (RING TYPE)	Locally Fabricated	1	ea	12,000.00	12,000.00
2	1U Horizontal Management Panel, sand paper	Locally Fabricated	2	ea	480.00	960.00
					Sub-Total for C :	**12,960.00**
D	**Labors & Others**					
1	Mobilization / Demobilization	-	1	lot	20,000.00	20,000.00
2	Permits, Insurance, Bond and the likes.	-	1	lot	20,000.00	20,000.00
3	Labor for installation of SCS which includes cable pulling, termination, harnessing, racks, labeling, testing & commissioning.	-	1	lot	100,000.00	100,000.00
4	Labor for installation of horizontal roughing-ins materials such as cable tray, IMC pipes, metal flexible, hangers, supports and other consumable items.	-	1	lot	120,000.00	120,000.00
5	Engineering and Documentation for Handover Documents & As-built Plans	-	1	lot	50,000.00	50,000.00
					Sub-Total for D :	**310,000.00**
E	**Grand Total(A + B + C + D)**					**741,734.00**

LANTRO PHILS., INC.
420 Unit D, F. Legaspi Street Maybunga
Pasig City, Philippines
Tel: 632 621 8619
Fax: 632 470 4740

To: **Pricon Microelectronics, Inc**

QUOTATION

Our Ref	MNMNQU-1802665-Rev0-P
Date	22-Jan-19
Total page	2

Attn: **Ricardo C. Martin III**
Email: rcmartin@pricon.ph
Trunkli **(63)2-843-0870 local 228**

ITEM	PARTICULARS	PART NO.	QTY	U/M	U/P (PHP)	Total Amount (PHP)
	RE: Pricon @ Canlubang Laguna Supply & Install Panduit Cat6					
	Terms & Conditions					
1 .	All prices quoted are in **Philippines Peso**.					
2 .	All prices quoted herein are **NONVAT**					
3 .	Delivery Lead-time for Cabling Components : - On-stock, within **1-2 weeks** from the date of receipt of downpayment - Ex-stock, **6-8 weeks** from the date of receipt of downpayment - All purchase orders are subject to availability and prior sales					
4 .	Schedule of Project LanTro shall mobilize within five (5) days from the receipt of Notice of Award or Purchase Order. The entire project can be completed within Fifteen to twenty (15-20) working days unless all dependencies are cleared such as civil works and fitting out works.					
5 .	The design and configuration is based on the customer's present requirements. If the customer changes their requirement prior to or after acceptance of LanTro's proposal, LanTro reserves the right to amend its proposal, including the products and prices.					
6 .	Validity : **Fifteen (15) days** from the date of submission - LanTro reserves the right to change the price after the validity period has expired.					
7 .	Payment Terms **30% Downpayment upon Receipt of Purchase Order** **60% Progress Billing** **10% Upon Completion of project** Note: Payment is due within fifteen (15) days from date of invoice. All overdue payments will be subject to late payment charge of one and a half percent (1.5%) of the outstanding amount per month or the maximum amount permitted by law whichever is less.					
8 .	Cancellation / Termination - If the client request cancellation of an order five days after the issuance of Purchase Order, Lantro will charge the total amount of materials already ordered to the supplier. The materials ordered will be given to the client. - If the client cancel the services after Lantro has begun services under the Scope of Work, the client will be responsible for paying fifty percent (50%) of the total agreement price. The customer will be also responsible for paying all incurred, unrecoverable travel and related expenses of Consultant(s), any third-party vendors, or sub-contractors who have provided services under this agreement.					
11 .	1-year Workmanship Warranty Lantro Phil's. Inc., when awarded the contract to supply and install the structured cabling systems for Pricon, Canlubang Laguna, Phils will provide 1- year workmanship warranty on the installed structured systems and the scope of work comprises the followings: * To troubleshoot any reported cable fault (copper & fiber). * To replace damaged SCS components (copper & Fiber) (material cost to be charged separately) * Any materials required or/and additional work to be done but not specified in the Contract (e.g. Relocation of inter-rack points) will be charged accordingly at an agreed price. Responsibilities of LANTRO PHILS., INC. are as follows - In general, response time will be next working day upon receipt of the Job Request. Where there is urgent requirement, immediate response is guaranteed; but limited to one request per quarter.					

LANTRO PHILS. INC.

Al Ben Z. Mangahas
Project Engineer

Emmard Hudson Legaspi
Operations Manager

Acceptance By :

Name, Signature, Co. Stamp & Date