ENGAUGE HYDRAULICS CORP.
L33, B37, 2nd Greenstone St.,
Green Valley Subdivision, Molino,
Bacoor, Cavite, 4102 Philippines
Tel : +632-7104981
Fax : +632-6642847
Email : engaugehyd@yahoo.com

REF:
DATE 05-Jun-2018
FAX NO.
TEL. NO.
EMAIL rebvale@pricon.ph

Costumer : **Pricon Microelectronics, Inc.**
Address : LISP1, Cabuyao, Laguna
Attention : Ms. Rebecca D. Valenzuela

QUOTATION

Item	Description / Part No.	Qty	U/M	Unit Price	Amount
1	Labor Cost for Resealing and rehosing for Sodick	1	Lot	25,000.00	25,000.00
	injection machine TR55EH2 #7C				
	Scope of works.				
	1. Machine function test, observe leaks.				
	2. Machine Shut Down.				
	3. Strip machine components and hoses tagging.				
	4. Inspect, clean, and overhaul individual components.				
	5. Replace hydraulic hoses and component O-rings.				
	6. Install and testing.				
	7. Machine Commissioning				
	Note:				
	Hydraulic hose and O-ring prices are not included.				
	Parts found defective will be quoted separately.				

TERMS AND CONDITIONS

Delivery : 3-4 days upon receipt of firm order.		25,000.00
Payment : 30 days		
Validity : 30 days		
Prepared By : Ver Casas		**Final Amount PHP**
Sales Engineer	Conforme	VAT Excluded