DEZERTECH ENGINEERING & GENERAL MERCHANDISE

General Building, General Engineering, Electrical Works, Mechanical Works
Electromechanical Works, Airconditioning & Refrigeration, Ducting & Fabrication Works,
Communication Facilities, Fire Protection & FDAS Works, Elevator & Escalator Works, Road & Reblocking Works,
Land Development & Heavy Equipment Rentals, Commerce / Trading of Construction & Industrial Supplies,
Engineering Consultancy, Plotting & Blue Printing Services
PCAB LICENSE- GENERAL CONTRACTOR- DESIGN & CONSTRUCT

Office: Central Compound, Crossing, Calamba City
Office Yard: Lot 5, Blk 7, Lakeview, Rosal St. Chipeco Ave. Extn., Halang, Calamba City
Tel No. (049) 530-7461, Mobile No. 0922-890-5824
Email: dezertech_ega@yahoo.com

QUOTATION

QUOTATION No. 03292022 - 3

Customer: PRICON MICROELECTRONICS, INC.
Address: #14 Ampere St., LISPP - 1, Bo. Diezmo, Cabuyao, Laguna
Attention: **Mr. Joel C. Padullo** / Vice-President for Operatio
Thru: **Mr. Roberto M. Pacheco** / Facilities Manager
Ms. Anna Marie Nueva / Purchasing Asst. Manager

Date Prepared: March 29, 2022
Validity : 30 days

ITEM	QUANTITY	PARTICULARS	UNIT COST	SUB TOTAL
1	1 LOT	**SUPPLY OF LABOR & MATERIALS FOR VARIATION ORDER FOR ELECTRICAL WORKS IN PMI GRINDING AREA** ***(SEE ATTACHED BILL OF MATERIALS)*** **********NF**********	Php 117,042.87	Php 117,042.87
			TOTAL PRICE	Php 117,042.87

TERMS AND CONDITIONS:

* *Payment 50% down payment & 50% upon completion*
* *Project completion 45 working days subject to delay beyond our control*
* *Exclusive of temporary space for material storage, power & water supply during the entire construction*
* *Other works not stated above shall be subject to a separate client conforme / PO before the execution of works.*

PROJECT COST Php 117,042.87
VAT ZERO RATED

Prepared by:	Noted by:	Approved by:
djsa	asa	Edezer G. Arias, AMO, GM

Conforme:

Signature Over Printed Name

Thank you for giving us the chance to quote the above item/s as per your deemed request. For any clarification, please send your queries to dezer_tech@yahoo.com.ph or please call (049) 545-6522. We will be glad to hear from you.

BILL OF MATERIALS
PROJECT TITTLE: **SUPPLY OF LABOR & MATERIALS FOR VARIATION ORDER FOR ELECTRICAL WORKS IN PMI GRINDING AREA**

CONSTRUCTION DETAILS: **ELECTRICAL WORKS**

ITEM	SCOPE & MATERIALS	QTY	UNIT	MATERIALS				LABOR				TOTAL			
				UNIT COST		AMOUNT		UNIT COST		AMOUNT		UNIT COST		AMOUNT	
I.	**Additional Electrical Works**														
	A. Electrical Panel with Circuit Breakers														
1	Electrical Panel, NEMA-1 Enclosure (1.5mm thick), with grounding bus and universal lugs, Powder-coated Main: 200 AT / 250 AT, 3-Φ Branches: 2 x 60 AT / 100 AF, 3-Φ 4 x 30 AT / 100 AF, 3-Φ	1	ass'y	Php	54,155.00	Php	54,155.00	Php	18,954.25	Php	18,954.25	Php	73,109.25	Php	73,109.25
2	Electrical Panel, NEMA-1 Enclosure (1.5mm thick), with grounding bus and universal lugs, Powder-coated Main: 60 AT / 250 AT, 3-Φ Branches: 2 x 20 AT / 100 AF, 1-Φ	1	ass'y	Php	19,760.00	Php	19,760.00	Php	6,916.00	Php	6,916.00	Php	26,676.00	Php	26,676.00
3	Consumables	1	lot	Php	5,000.00	Php	5,000.00	Php	1,750.00	Php	1,750.00	Php	6,750.00	Php	6,750.00
	B. Feeder Lines														
1	80mm2 THHN Wire	60.00	m	Php	840.00	Php	50,400.00	Php	294.00	Php	17,640.00	Php	1,134.00	Php	68,040.00
2	38mm2 THHN Wire	20.00	m	Php	399.00	Php	7,980.00	Php	139.65	Php	2,793.00	Php	538.65	Php	10,773.00
3	14mm2 THHN Wire	15.00	m	Php	147.00	Php	2,205.00	Php	51.45	Php	771.75	Php	198.45	Php	2,976.75
4	3.5mm2 THHN Wire	5.00	m	Php	36.75	Php	183.75	Php	12.86	Php	64.31	Php	49.61	Php	248.06
5	Consumables	1.00	lot	Php	2,500.00	Php	2,500.00	Php	875.00	Php	875.00	Php	3,375.00	Php	3,375.00
											SUB-TOTAL FOR ITEM I			Php	**191,948.06**
LESS:	**ITEMS INCLUDED IN THE ORIGINALLY-SUBMITTED QUOTATION / BOM (BOXED/HIGHLIGHTED)**														
	A. Circuit Breakers (MCCB only)														
1	60 AT, 3-Φ, Circuit Breakers	3	unit	Php	6,682.69	Php	20,048.07	Php	2,338.94	Php	7,016.82	Php	9,021.63	Php	27,064.89
2	30 AT, 3-Φ, Circuit Breakers	5	unit	Php	3,341.34	Php	16,706.70	Php	1,169.47	Php	5,847.35	Php	4,510.81	Php	22,554.05
3	40 AT, 1-Φ, Circuit Breakers	2	unit	Php	4,455.12	Php	8,910.24	Php	1,559.29	Php	3,118.58	Php	6,014.41	Php	12,028.82
4	30 AT, 1-Φ, Circuit Breakers	3	unit	Php	3,341.34	Php	10,024.02	Php	1,169.47	Php	3,508.41	Php	4,510.81	Php	13,532.43
5	Consumables	1	lot	Php	3,500.00	Php	3,500.00	Php	1,225.00	Php	1,225.00	Php	4,725.00	Php	4,725.00
											SUB-TOTAL FOR ITEM II			Php	**79,905.19**

A.	**DIFFERENCE BETWEEN ITEMS I and II**	**Php**	**112,042.87**
B..	**GENERAL REQUIREMENTS**		
	a. Mobilization / Demobilization	Php	5,000.00
	b. Site Enclosure (Blue sack)	Php	-
	c. PEZA Permit (Inclusive of Design, Plans Preparation - Signed & Sealed, As Built- Hard Copy & Soft Copy, SOA and other fees to be shouldered by PMI)	Php	-
	d. Site expenses	Php	-
	e. Safety Requirements	Php	-
C.	**INDIRECT COST (Overhead, Supervision)**	Php	-
D.	**CONTRACTOR'S PROFIT**	Php	-
E.	**SUB TOTAL**	Php	117,042.87
F.	***VAT*** *0%*	*Php*	-
	ESTIMATED TOTAL COST OF PROJECT	**TOTAL PROJECT PRICE Php**	**117,042.87**

MODE OF PAYMENT
Down Payment *50%*
Upon Completion *50%*

Approved by:

Edezer G. Arias
General Manager /AMO
DEZERTECH ENGINEERING & GEN. MDSE
PCAB LICENSE CONTRACTOR
General Building, General Engineering, Electrical Works,
Mechanical Works, Communication Facilities, Fire Protection & FDAS Works
Elevator & Escalator, Electro Mechanical Works, Airconditioning & Refrigeration,
& Heavy Equipment Rentals, Road, Highway, Pavement, Railway, Airport Horizontal Structure,
Bridges, Irigation and Flood Control, Water Supply, Building & Industrial
Plant, Sewerage and Sewage Treatment / Disposal Plant, Water Treatment Plant
and System, Park, Play Ground and Recreation Work