DEZERTECH ENGINEERING & GENERAL MERCHANDISE

General Building, General Engineering, Electrical Works, Mechanical Works
Electromechanical Works, Airconditioning & Refrigeration, Ducting & Fabrication Works,
Communication Facilities, Fire Protection & FDAS Works, Elevator & Escalator Works, Road & Reblocking Works,
Land Development & Heavy Equipment Rentals, Commerce / Trading of Construction & Industrial Supplies,
Engineering Consultancy, Plotting & Blue Printing Services
PCAB LICENSE- GENERAL CONTRACTOR- DESIGN & CONSTRUCT

Office: Central Compound, Crossing, Calamba City
Office Yard: Lot 5, Blk 7, Lakeview, Rosal St. Chipeco Ave. Extn., Halang, Calamba City
Tel No. (049) 530-7461, Mobile No. 0922-890-5824
Email: dezertech_ega@yahoo.com

QUOTATION

QUOTATION No. 06032022-4

Customer: PRICON MICROELECTRONICS, INC.
Address: #14 Ampere St. SEPZ, LISP1, Bo. Diezmo, Cabuyao City

Date Prepared: June 3, 2022
Validity : 30days

Attention: Sir Joel C. Padullo
Vice-President for Operations

ITEM	QUANTITY	PARTICULARS	UNIT COST	SUB TOTAL
1	1 LOT	SUPPLY OF LABOR & MATERIALS FOR THE VARIATION DUE TO MACHINE RELOCATION (GRINDING AREA) *ELECTRICAL AND MECHANICAL WORKS* *(see attached BOM)* **********NF**********	₱ 325,582.65	₱ 325,582.65
			TOTAL PRICE	₱ 325,582.65
			less 5% DISCOUNT	₱ 16,279.13
			PROJECT COST	₱ 309,303.52
			VAT ZERO-RATED	

TERMS AND CONDITIONS:

* *Payment 50% down payment & 50% upon completion.*
* *Project completion as per arrangement schedule.*
* *Additional works other than the stated list of scope of works shall be implemented only upon written authorization and shall be subject to a separate quotation and Purchase Order.*
* *Exclusive of temporary space for material storage, power & water supply during the entire construction.*

Prepared by:	Noted by:	Approved by:
djsa	asa	Edezer G. Arias, AMO, GM

email copy only original copy with signed to be hand-carried

Conforme:

Signature Over Printed Name

Thank you for giving us the chance to quote the above item/s as per your deemed request. For any clarification, please send your queries to dezer_tech@yahoo.com.ph or please call (049) 545-6522. We will be glad to hear from you.

BILL OF MATERIALS

PROJECT TITLE: SUPPLY OF LABOR & MATERIALS FOR THE ELECTRICAL AND MECHANICAL WORKS DUE TO MACHINES RELOCATION ACTIVITIES (GRINDING AREA)

CONSTRUCTION DETAILS: ELECTRICAL AND MECHANICAL WORKS

ITEM	SCOPE & MATERIALS	QTY	UNIT	MATERIALS		LABOR		TOTAL		
				UNIT COST	AMOUNT	UNIT COST	AMOUNT	UNIT COST	AMOUNT	
I.	**ELECTRICAL WORKS**									
A.	**2 - SPINDLE MACHINE 1 (MAY 2022)**									
1	RELOCATION OF POWER SUPPLY DROPS FOR ACCESSORIES (220V AND 100V)	1.00	lot			₱ 3,500.00	₱ 3,500.00	₱ 3,500.00	₱ 3,500.00	
2	RELOCATION OF POWER SUPPLY DROPS FOR MC (200 V, 3-Φ)	1.00	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
3	CONSUMABLES	1.00	lot	₱ 1,000.00	₱ 1,000.00	₱ 400.00	₱ 400.00	₱ 1,400.00	₱ 1,400.00	
										₱ 7,000.00
B.	**PROVISION FOR ADDITIONAL MACHINES (CHANGE LOCATION) (JUNE & JULY 2022) - 200V SUPPLY**									
	1 NEW MACHINE (CNC 8)									
	STATUS: NO EXISTING ELECTRICAL LAYOUT PROVISION (NEW INSTALLATION)									
1	40 AT, 3-Φ ECB (additional panel, tap to bus bar of DP-7))	1	ass'y	₱ 10,247.12	₱ 10,247.12	₱ 4,098.85	₱ 4,098.85	₱ 14,345.97	₱ 14,345.97	
2	8 mm2 THHN	1	box	₱ 14,160.00	₱ 14,160.00	₱ 5,664.00	₱ 5,664.00	₱ 19,824.00	₱ 19,824.00	
3	3.5 mm2 THHN (GREEN)	1	box	₱ 5,500.00	₱ 5,500.00	₱ 2,200.00	₱ 2,200.00	₱ 7,700.00	₱ 7,700.00	
4	Ø 25 mm EMT	8	len	₱ 621.82	₱ 4,974.53	₱ 248.73	₱ 1,989.81	₱ 870.54	₱ 6,964.34	
5	Ø 25 mm EMT FITTINGS	1	lot	₱ 1,000.00	₱ 1,000.00	₱ 400.00	₱ 400.00	₱ 1,400.00	₱ 1,400.00	
6	HANGERS AND BRACKET	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
7	CONSUMABLES	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
										₱ 54,434.31
	2 OLD 6-SPINDLE MACHINE									
	STATUS: WITH EXISTING ELECTRICAL SUPPLY (SEE DETAILS BELOW) - NON-DEDUCTIVE, CANNOT BE REUSED									
1	30 mm2 THHN	67.5	m							
2	8 mm2 THHN	22.5	m							
3	Ø 38 mm EMT	8	len							
4	Ø 38 mm EMT FITTINGS	1	lot							
5	HANGERS AND BRACKET	1	lot							
	SCOPE OF WORKS: JUSTIFICATION - NEW ELECTRICAL INSTALLATION (RE-WIRE). EXISTING WIRES AND CONDUITS ARE SHORT TO BE RE-USED FOR (SOON-TO-BE RELOCATED) MACHINE									
1	30 mm2 THHN	82.5	m	₱ 350.00	₱ 28,875.00	₱ 140.00	₱ 11,550.00	₱ 490.00	₱ 40,425.00	
2	8 mm2 THHN	27.5	m	₱ 141.60	₱ 3,894.00	₱ 56.64	₱ 1,557.60	₱ 198.24	₱ 5,451.60	
3	Ø 40 mm EMT	2	len	₱ 1,062.82	₱ 2,125.64	₱ 425.13	₱ 850.26	₱ 1,487.95	₱ 2,975.90	
4	Ø 40 mm EMT FITTINGS	1	lot	₱ 1,000.00	₱ 1,000.00	₱ 400.00	₱ 400.00	₱ 1,400.00	₱ 1,400.00	
5	HANGERS AND BRACKET	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
6	CONSUMABLES	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
										₱ 54,452.50
	3 NEW 6-SPINDLE MACHINE (JUNE 2022)									
	STATUS: WITH EXISTING ELECTRICAL SUPPLY (SEE DETAILS BELOW) - NON-DEDUCTIVE, CANNOT BE REUSED									
1	14 mm2 THHN	53.7	m							
2	3.5 mm2 THHN	17.9	m							
3	Ø 32 mm EMT	8	len							
4	Ø 32 mm EMT FITTINGS	1	lot							
5	HANGERS AND BRACKET	1	lot							
	SCOPE OF WORKS: NEW ELECTRICAL INSTALLATION (RE-WIRE). EXISTING WIRES AND CONDUITS ARE SHORT TO BE RE-USED FOR (SOON-TO-BE RELOCATED) MACHINE									
1	14 mm2 THHN	72	m	₱ 217.12	₱ 15,632.64	₱ 86.85	₱ 6,253.06	₱ 303.97	₱ 21,885.70	
2	3.5 mm2 THHN	24	m	₱ 40.00	₱ 960.00	₱ 16.00	₱ 384.00	₱ 56.00	₱ 1,344.00	
3	Ø 32 mm EMT	4	len	₱ 750.00	₱ 3,000.00	₱ 300.00	₱ 1,200.00	₱ 1,050.00	₱ 4,200.00	
4	Ø 32 mm EMT FITTINGS	1	lot	₱ 1,000.00	₱ 1,000.00	₱ 400.00	₱ 400.00	₱ 1,400.00	₱ 1,400.00	
5	HANGERS AND BRACKET	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
6	CONSUMABLES	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
										₱ 33,029.70

4 NEW 6-SPINDLE MACHINE (JULY 2022)

STATUS: WITH EXISTING ELECTRICAL SUPPLY (SEE DETAILS BELOW) - NON-DEDUCTIVE, CANNOT BE REUSED

1	14 mm2 THHN	69	m
2	3.5 mm2 THHN	23	m
3	Ø 32 mm EMT	8	len
4	Ø 32 mm EMT FITTINGS	1	lot
5	HANGERS AND BRACKET	1	lot

SCOPE OF WORKS: NEW ELECTRICAL INSTALLATION (RE-WIRE). EXISTING WIRES AND CONDUITS ARE SHORT TO BE RE-USED FOR (SOON-TO-BE RELOCATED) MACHINE

1	14 mm2 THHN	85.5	m	₱	217.12	₱	18,563.76	₱	86.85	₱	7,425.50	₱	303.97	₱	25,989.26	
2	3.5 mm2 THHN	28.5	m	₱	40.00	₱	1,140.00	₱	16.00	₱	456.00	₱	56.00	₱	1,596.00	
3	Ø 32 mm EMT	6	len	₱	750.00	₱	4,500.00	₱	300.00	₱	1,800.00	₱	1,050.00	₱	6,300.00	
4	Ø 32 mm EMT FITTINGS	1	lot	₱	1,000.00	₱	1,000.00	₱	400.00	₱	400.00	₱	1,400.00	₱	1,400.00	
5	HANGERS AND BRACKET	1	lot	₱	1,500.00	₱	1,500.00	₱	600.00	₱	600.00	₱	2,100.00	₱	2,100.00	
6	CONSUMABLES	1	lot	₱	1,500.00	₱	1,500.00	₱	600.00	₱	600.00	₱	2,100.00	₱	2,100.00	
																₱ 39,485.26

5 220V, 100V AND 200V OUTLETS FOR MACHINE ACCESSORIES

SCOPE OF WORKS: RELOCATION OF OUTLETS FOR MACHINE ACCESSORIES (CONDUIT DROPS AND COs ARE TO BE RE-USED)

1	3.5 mm2 THHN (RED)	1	box	₱	5,500.00	₱	5,500.00	₱	2,200.00	₱	2,200.00	₱	7,700.00	₱	7,700.00	
2	3.5 mm2 THHN (BLUE)	1	box	₱	5,500.00	₱	5,500.00	₱	2,200.00	₱	2,200.00	₱	7,700.00	₱	7,700.00	
3	3.5 mm2 THHN (BLACK)	1	box	₱	5,500.00	₱	5,500.00	₱	2,200.00	₱	2,200.00	₱	7,700.00	₱	7,700.00	
4	3.5 mm2 THHN (WHITE)	1	box	₱	5,500.00	₱	5,500.00	₱	2,200.00	₱	2,200.00	₱	7,700.00	₱	7,700.00	
5	3.5 mm2 THHN (GREEN)	1	box	₱	5,500.00	₱	5,500.00	₱	2,200.00	₱	2,200.00	₱	7,700.00	₱	7,700.00	
6	Ø 20 mm EMT	15	len	₱	275.00	₱	4,125.00	₱	110.00	₱	1,650.00	₱	385.00	₱	5,775.00	
7	Ø 20 mm EMT FITTINGS	1	lot	₱	1,000.00	₱	1,000.00	₱	400.00	₱	400.00	₱	1,400.00	₱	1,400.00	
8	HANGERS AND BRACKET	1	lot	₱	1,500.00	₱	1,500.00	₱	600.00	₱	600.00	₱	2,100.00	₱	2,100.00	
9	CONSUMABLES	1	lot	₱	1,500.00	₱	1,500.00	₱	600.00	₱	600.00	₱	2,100.00	₱	2,100.00	
																₱ 49,875.00

II. MECHANICAL WORKS

A. COMPRESSED DRY AIR

1	ADDITIONAL AIR SUPPLY DROPS	5.00	drop	₱	1,750.00	₱	8,750.00	₱	700.00	₱	3,500.00	₱	2,450.00	₱	12,250.00	
2	CONSUMABLES	1.00	lot	₱	1,000.00	₱	1,000.00	₱	400.00	₱	400.00	₱	1,400.00	₱	1,400.00	
																₱ 13,650.00

B. FLEXIBLE EXHAUST PIPES AND VOLUME DAMPERS

1	RELOCATION OF EXHAUST DROPS / EXTENSION OF EXHAUST PIPES	4.00	drop	₱	5,500.00	₱	22,000.00	₱	2,200.00	₱	8,800.00	₱	7,700.00	₱	30,800.00	
2	CONSUMABLES	1.00	lot	₱	2,000.00	₱	2,000.00	₱	800.00	₱	800.00	₱	2,800.00	₱	2,800.00	
																₱ 33,600.00

A.	**GRAND TOTAL OF ITEMS I AND II**		Php	285,526.76
B..	**GENERAL REQUIREMENTS**			
	a. Mobilization / Demobilization		Php	6,500.00
	b. Temporary facilities		Php	-
	c. Site expenses		Php	-
	d. Safety Requirements		Php	5,000.00
C.	**INDIRECT COST (Overhead, Supervision)**		Php	-
D.	**CONTRACTOR'S PROFIT**		Php	28,552.65
E.	**SUB TOTAL**		Php	325,582.65
F.	***VAT***	*0%*	*Php*	-
	ESTIMATED COST OF PROJECT		**Php**	**325,582.65**
	MODE OF PAYMENT			
	Down Payment	*50%*		
	Upon Completion	*50%*		

Engr. Alvin M. Mancilla
Operations Manager
DEZERTECH ENGINEERING & GEN. MDSE
PCAB-LICENSED CONTRACTOR

Edezer G. Arias
General Manager /AMO
DEZERTECH ENGINEERING & GEN. MDSE
PCAB-LICENSED CONTRACTOR
DESIGN & CONSTRUCT
General Building, General Engineering, Electrical Works,
Mechanical Works, Communication Facilities, Fire Protection & FDAS Works
Elevator & Escalator, Electro Mechanical Works, Airconditioning & Refrigeration,
& Heavy Equipment Rentals, Road, Highway, Pavement, Railway, Airport Horizontal Structure,
Bridges, Irigation and Flood Control, Water Supply, Building & Industrial
Plant, Sewerage and Sewage Treatment / Disposal Plant, Water Treatment Plant
and System, Park, Play Ground and Recreation Work, Land Development, Heavy Equipment Rentals
Commerce & Trading of Construction & Industrial Supplies, Plotting & Blue Printing Services