LANTRO PHILS., INC.
420 Unit D, F. Legaspi Street Maybunga
Pasig City, Philippines
Tel: 632 621 8619
Fax: 632 470 4740

To: **Pricon Microelectronics, Inc**

QUOTATION

Our Ref	MNMNQU-1901888-Rev0-P
Date	27-Sep-19
Total page	1

Attn: **Mr. Ricardo C. Martin III**
Email: rcmartin@pricon.ph
Tel no. **(63)2-843-0870 local 228**

ITEM	PARTICULARS	PART NO.	QTY	U/M	U/P (PHP)	Total Amount (PHP)
RE:	**Pricon @ Cabuyao, Laguna Supply & Install @ FANUC Room**					
A	**Horizontal Cabling @ FANUC Room (addtnl' 6 nodes)**					
1	Belden, STP 4C, AWG 22	8723	1	box	18,360.00	18,360.00
2	Belden® KeyConnect Straight Patch Panel 24-Port 1U Unloaded	AX106504-AP	1	ea	1,560.00	1,560.00
3	Belden® KeyConnect Category-6+ Information Outlet (Blue)	AX101326	12	ea	180.00	2,160.00
4	Belden Cat 6 RJ45 with boots	AP700008	4	ea	54.00	216.00
5	Belden® IBDN Patch Cord Category-6 2.0 Meters (Blue)	C6P9106002M	6	ea	330.00	1,980.00
6	Belden® IBDN Patch Cord Category-6 3.0 Meters (Blue)	C9P9106003M	6	ea	300.00	1,800.00
7	Belden® KeyConnect Simplex Faceplate (White)	AX102660	6	ea	90.00	540.00
8	Belden® KeyConnect Blank insert, Black	AX102660	18	ea	36.00	648.00
					Sub-Total for A :	**27,264.00**
B	**Horizontal Roughing-ins**					
1	EMT Pipe 1" x 10ft	-	15	ea	492.00	7,380.00
2	EMT Coupling 1"	-	30	ea	108.00	3,240.00
3	EMT Connector 1"	-	30	ea	66.00	1,980.00
4	EMT Pipe 3/4" x 10ft	-	15	ea	342.00	5,130.00
5	EMT Coupling 3/4"	-	30	ea	66.00	1,980.00
6	EMT Connector 3/4"	-	30	ea	54.00	1,620.00
7	Anchor Bolt 3/8"	-	60	ea	18.00	1,080.00
8	Plain Washer 3/8"	-	60	ea	4.80	288.00
9	Hexagonal Nut 3/8"	-	60	ea	4.80	288.00
10	Unistrutt Channel 1⅝ x 1⅝ x 10ft	-	2	ea	1,380.00	2,760.00
11	Unistrutt Clamp 1", Caddy	-	30	ea	78.00	2,340.00
12	Unistrutt Clamp 3/4", Caddy	-	40	ea	66.00	2,640.00
13	Amco Box	-	6	ea	48.00	288.00
14	Threaded Round bar 3/8 x 10ft	-	15	ea	150.00	2,250.00
15	Square Box 4 11/16" x 4 11/16" w/ cover	-	15	ea	120.00	1,800.00
16	1" Straight Connector	-	6	ea	42.00	252.00
18	Metal Flexible 1" 30mtrs/roll	-	1	reel	1,704.00	1,704.00
19	Velcro Ties, Black 10m /roll	-	2	reel	1,380.00	2,760.00
20	Cable Tie 550 x 8mm	-	1	pcs	600.00	600.00
21	Plastic Moulding 1" x 8ft	-	6	ea	138.00	828.00
					Sub-Total for B :	**41,208.00**
C	**Racks and Accessories**					
1	WALLMOUNT CABINET H=1FT(6RU) W=600mm X D=600mm ● 19" STANDARD OPENING SYSTEMS ● FRAMING & PANELLING GAUGE# 16 ● PLEXIGLASS FRONT DOOR W/PUSHLOCK ● DETACHABLE SIDE PANELS W/CAMLOCK ● FIXED TYPE BACK PANEL ● W/ 2 PCS EXHAUST FAN @ THE TOP PANEL ● W/ VERTICAL POWERSTRIP 4 C.O., 3 PRONG , 220V, 20AMP-FUSE CAPACITY ● W/ VERTICAL CABLE MANAGER @ THE BACK (RING TYPE) ● W/20 PCS. CAGENUT AND SCREWS ● BLACK (POWDER COATED) ● BOLTED TYPE	Locally Fabricated	1	ea	12,600.00	12,600.00
					Sub-Total for C :	**12,600.00**
D	**Labors & Others**					
1	Mobilization / Demobilization	-	1	lot	10,000.00	10,000.00
2	Permits, Insurance, Bond and the likes.	-	1	lot	5,000.00	5,000.00
3	Labor for installation of SCS which includes cable pulling, termination, harnessing, racks, labeling, testing & commissioning.	-	1	lot	20,000.00	20,000.00
4	Labor for installation of horizontal roughing-ins materials such as cable tray, IMC pipes, metal flexible, hangers, supports and other consumable items.	-	1	lot	20,000.00	20,000.00
5	Engineering and Documentation for Handover Documents & As-built Plans	-	1	lot	10,000.00	10,000.00
6	Labor for installation of IDF Wall Mount Cabinet	-	1	lot	20,000.00	20,000.00
					Sub-Total for D :	**85,000.00**
D	**Grand Total**					**166,072.00**

LANTRO PHILS., INC.
420 Unit D, F. Legaspi Street Maybunga
Pasig City, Philippines
Tel: 632 621 8619
Fax: 632 470 4740

To: **Pricon Microelectronics, Inc**

QUOTATION

Our Ref	MNMNQU-1901888-Rev0-P
Date	27-Sep-19
Total page	1

Attn: **Mr. Ricardo C. Martin III**
Email: rcmartin@pricon.ph
Tel no. **(63)2-843-0870 local 228**

ITEM	PARTICULARS	PART NO.	QTY	U/M	U/P (PHP)	Total Amount (PHP)
RE:	**Pricon @ Cabuyao, Laguna Supply & Install @ FANUC Room**					
	Terms & Conditions					
1 .	All prices quoted are in **Philippines Peso**.					
2 .	All prices quoted herein are **VAT EXCLUSIVE.**					
3 .	Delivery Lead-time for Cabling Components : - On-stock, within **1-2 weeks** from the date of receipt of downpayment - Ex-stock, **6-8 weeks** from the date of receipt of downpayment - All purchase orders are subject to availability and prior sales					
4 .	Schedule of Project LanTro shall mobilize within five (5) days from the receipt of Notice of Award or Purchase Order. The entire project can be completed within Three to five (3-5) working days unless all dependencies are cleared such as civil works and fitting out works.					
5 .	The design and configuration is based on the customer's present requirements. If the customer changes their requirement prior to or after acceptance of LanTro's proposal, LanTro reserves the right to amend its proposal, including the products and prices.					
6 .	Validity : **Fifteen (15) days** from the date of submission - LanTro reserves the right to change the price after the validity period has expired.					
7 .	Payment Terms **100% Upon Completion of Project** Note: Payment is due within fifteen (15) days from date of invoice. All overdue payments will be subject to late payment charge of one and a half percent (1.5%) of the outstanding amount per month or the maximum amount permitted by law whichever is less.					
8 .	Cancellation / Termination - If the client request cancellation of an order five days after the issuance of Purchase Order, Lantro will charge the total amount of materials already ordered to the supplier. The materials ordered will be given to the client. - If the client cancel the services after Lantro has begun services under the Scope of Work, the client will be responsible for paying fifty percent (50%) of the total agreement price. The customer will be also responsible for paying all incurred, unrecoverable travel and related expenses of Consultant(s), any third-party vendors, or sub-contractors who have provided services under this agreement.					

LANTRO PHILS. INC.

Maverick Humprey P. Elises
Project Engineer

_____
Emmard Hudson Legaspi
Operations Manager

Acceptance By :

Name, Signature, Co. Stamp & Date