ENGAUGE HYDRAULICS CORP.
L33, B37, 2nd Greenstone St.,
Green Valley Subdivision, Molino,
Bacoor, Cavite, 4102 Philippines
Tel : +632-87104981
Fax :
Email : engaugehyd@yahoo.com

REF:
DATE 24-Sep-2020
FAX NO.
TEL. NO.
EMAIL rebvale@pricon.ph

Costumer : **Pricon Microelectronics, Inc.**
Address : LISP1, Cabuyao, Laguna
Attention : Ms. Rebecca D. Valenzuela

QUOTATION

Item	Description / Part No.	Qty	U/M	Unit Price	Amount
1	Labor cost for transfer of 2-units 80-liter accumulator assy.	1	Lot	35,000.00	35,000.00
	for Nissei plastic injection machine with the following scope				
	of works.				
	1. Machine Shut Down 2-units Nissei machine				
	2. Depressurize accumulator hydraulic system				
	3. Remove damaged accumulator assy. Machine 1				
	4. Remove known working accumulator assy. Machine 2				
	5. Install working accumulator to Machine 1.				
	6. Install damaged accumulator to Machine 2.				
	7. Accumulator hydraulic pressure and nitrogen pressure				
	setting as per machine manual.				
	8. Machine testing and commissioning.				
	Note				
	1. Draining of hydraulic oil for both machine 1 and 2 to be				
	done by PMI.				
	2. Lifting straps and tackles to be provided by EHC.				
	3. Parts found defective will be quoted separately.				

TERMS AND CONDITIONS

Delivery : 1-2 days upon receipt of firm order.		35,000.00
Payment : 30 days		
Validity : 30 days		
Prepared By : Ver Casas		**Final Amount PHP**
Sales Engineer	Conforme	VAT Excluded