ENGAUGE HYDRAULICS CORP.
L33, B37, 2nd Greenstone St.,
Green Valley Subdivision, Molino,
Bacoor, Cavite, 4102 Philippines
Tel : +632-7104981
Fax : +632-6642847
Email : engaugehyd@yahoo.com

REF:
DATE 31-Oct-2019
FAX NO.
TEL. NO.
EMAIL rebvale@pricon.ph

Costumer : **Pricon Microelectronics, Inc.**
Address : LISP1, Cabuyao, Laguna
Attention : Ms. Rebecca D. Valenzuela

# QUOTATION

| Item | Description / Part No. | Qty | U/M | Unit Price | Amount |
|---|---|---|---|---|---|
| 1 | Labor cost for transfer of 2-units 80-liter accumulator assy. | 1 | Lot | 35,000.00 | 35,000.00 |
| | for Nissei plastic injection machine with the following scope | | | | |
| | of works. | | | | |
| | 1. Machine Shut Down 2-units Nissei machine | | | | |
| | 2. Depressurize accumulator hydraulic system | | | | |
| | 3. Remove damaged accumulator assy. Machine 1 | | | | |
| | 4. Remove known working accumulator assy. Machine 2 | | | | |
| | 5. Install working accumulator to Machine 1. | | | | |
| | 6. Install damaged accumulator to Machine 2. | | | | |
| | 7. Accumulator hydraulic pressure setting. | | | | |
| | 8. Machine testing and commissioning. | | | | |
| | | | | | |
| | | | | | |
| | Note | | | | |
| | 1. Daining of hydraulic oil for both machine 1 and 2 to be | | | | |
| | done by PMI. | | | | |
| | 2. Lifting straps and tackles to be provided by EHC. | | | | |
| | 3. Parts found defective will be quoted separately. | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

TERMS AND CONDITIONS

| | | |
|---|---|---|
| Delivery : 1-2 days upon receipt of firm order. | | 35,000.00 |
| Payment : 30 days | | |
| Validity : 30 days | | |
| Prepared By : Ver Casas | | **Final Amount PHP** |
| Sales Engineer | Conforme | VAT Excluded |