SERG TECHNOLOGIES INC.
Harrison Mansion F. B. Harrison Pasay City
VAT Reg. TIN: 009-854-016-000

Reference: SERG-0105-2020

Project Name: **PRICON MICROELECTRONICS**
Project Loc: **Pricon (Office Cabuyao)**
Date **07/10/2020**
Subject: **1 node LAN cabling for CCTV in TS Warehouse Contact Retainer Area**

Dear Sir/Mam ,
Greetings, Thank you for the opportunity to provide you with this proposal.
We sincerely appreciate the confidence and trust you put into our products and services.

In compliance with your request and/or requirement, we are pleased to sumbit to you our proposal for your consideration; in the amount stated below together with our terms and conditions, which upon confirmation will be served as a valid contract.

We are very looking forward to serving you very soon.

ITEMS	DESCRIPTION	U/Q	U/M	Mat'l Unit Cost	TOTAL COST (Php)
I.GENERAL REQUIREMENTS					
1	Mobilization/ demobilization	1	lot	4,500.00	4,500.00
2	Beleting Cost	1	lot	3,750.00	3,750.00
			Sub total I.		**8,250.00**
Scope:					
II. Structured Cabling System Components					
Item					
1	Panduit UTP Cable cat6 4 Pairs (NUC6C04BU-C)	0.5	box	10,312.50	5,156.25
2	RG 45 Connector	2	pcs	114.00	228.00
			Sub total II.		**PHP 5,384.25**
III. Roughing-Ins Materials					
1	EMT Pipe 1/2"Ø with fittings	6	lgts	372.00	2,232.00
2	PVC Flexible Conduit ¾"Ø	2	mtrs	23.25	46.50
3	Metal Square box with cover	1	pcs	130.50	130.50
4	Utility box	1	pcs	87.00	87.00
5	Metal C-Clamp 1/2"	11	pcs	23.63	259.88
6	Electrical tape	1	pc	55.50	55.50
7	G.I Wire #16	1	kilo	136.50	136.50
8	Miscellaneous Consumables	1	lot	500.00	500.00
9	Hanger and Supports	1	lot	1,500.00	1,500.00
			Sub total III.		**PHP 4,947.88**
IV. Service Engineering					
1	1. Installation of roughing-ins with suffient hangers and supports; 2. Cable Pulling, End to end Termination; 3. Testing and commissioning (with printable test results).	1	lot	10,000.00	10,000.00
			Sub total IV.		**PHP 10,000.00**
			Total Amount Vat Ex.		**PHP 28,582.13**

* Proposal cost is Exclusive of Permits processing cost , PEZA requirements and Sign and Sealed Asbuit Plan if require or needed.

SERVICE LEVEL SUPPORT

In line with our commitment in providing our customers the highest level of support we will give the following value-added maintenance services that would complement our networking and cabling solution.

1. Provide customer support on the installed cabling system for One (1) year from date of purchase. This is on top of the standard warranty for all products supplied.

2. Additional or changes to the existing system that may be necessarily required which is not covered by the contract shall be arranged and discussed with the customer to be treated as a separate service.

WARRANTY

The following warranty applies:

1. One (1) year workmanship warranty and FREE Maintenance Service
2. Twenty (20) years standard product warranty for cables and components

PAYMENT TERMS AND CONDITIONS

1. Payment- - **Fif**ty percent (50%) Downpayment
Fifty (50%) Upon Completion

2. Price Validity - Thirty (30) Days from the Quotation Date

3. Availability - On stock items: Three (3) business days.
Special order items: 30 to 45 days upon receipt of confirmed purchase order.

4. Cancellation - There will be Thirty Percent (30%) payment upon the cancellation of Purchase Order.

5. Other Consideration - Any other works and supply not specified in this proposal will be discussed and billed separately.

Thank you very much.

Sincerely yours,

Jayson R. Marasigan
Sales Director
SERG Technologies Inc.
Harrison Mansion F.B. Harrison Pasay City
Mobile: 09566090260
Email: sales@serg-technologies.com
Email: sergtechnologiesinc@gmail.com

Conforme:

Signature over Printed Name