SERG TECHNOLOGIES INC.
Harrison Mansion F. B. Harrison Pasay City
VAT Reg. TIN: 009-854-016-000

Reference: SERG-0140-2021

Project Name: **PRICON MICROELECTRONICS**
Project Loc: **Pricon (Office Cabuyao)**
Date **04/28/2021**
Subject: **SUPPLY AND INSTALLATION OF 3 LAN PORTS AT CN171**

Dear Sir/Mam ,
Greetings, Thank you for the opportunity to provide you with this proposal.
We sincerely appreciate the confidence and trust you put into our products and services.

In compliance with your request and/or requirement, we are pleased to sumbit to you our proposal for your consideration; in the amount stated below together with our terms and conditions, which upon confirmation will be served as a valid contract.

We are very looking forward to serving you very soon.

ITEMS	DESCRIPTION	U/Q	U/M	Mat'l Unit Cost	TOTAL COST (Php)
I.GENERAL REQUIREMENTS					
1	Mobilization/ demobilization	1	lot	12,500.00	12,500.00
		Sub total I.			**12,500.00**
Scope:					
II. Structured Cabling System Components					
Item					
1	Panduit UTP Cable cat6 4 Pairs	1	box	10,312.50	10,312.50
2	Panduit Information Outlet Cat6	3	pcs	437.50	1,312.50
3	UTP Patch Cable Cat6 2 ft(IDF Patching)	3	pcs	578.20	1,734.60
4	Faceplate Simplex	3	pcs	121.80	365.40
		Sub total II.			**PHP 13,725.00**
III. Roughing-Ins Materials					
1	EMT Pipe 1"Ø with fittings	7	lgts	735.00	5,145.00
2	EMT Pipe 3/4"Ø with fittings	4	lgts	595.00	2,380.00
3	PVC Moding 3/4"	3	L	165.00	495.00
4	Full Threaded Round Bar	8	L	264.00	2,112.00
5	Unit strut channel	2	L	1,155.00	2,310.00
6	Uni strut clamp 1"	14	pairs	66.00	924.00
7	Uni strut clamp 20mm	25	pairs	58.50	1,462.50
8	Expansion bolt	25	pcs	17.50	437.50
9	Nuts and washer 3/8"	25	pcs	5.60	140.00
10	Metal Square box with cover	5	pcs	161.00	805.00
11	Fabriocated Metal Support	3	pcs	1,275.00	3,825.00
12	Beam Clamps	10	pcs	91.00	910.00
13	FS box	3	pcs	371.00	1,113.00
14	Electrical tape	2	pc	51.80	103.60
15	Masking Tape	1	pcs	49.00	49.00
16	G.I Wire #16	1	kilo	127.40	127.40
17	Miscellaneous Consumables/ Supports and brackets	1	lot	1,500.00	1,500.00
		Sub total III.			**PHP 23,839.00**
IV. Service Engineering					
1	Cable Pulling, End to end Termination;Testing and commissioning (with	1	lot	25,000.00	25,000.00

Sub total IV.	**PHP 25,000.00**
Total Amount Vat Ex.	**PHP 75,064.00**

* Proposal cost is Exclusive of Permits processing cost , PEZA requirements and Sign and Sealed Asbuit Plan if require or needed.

SERVICE LEVEL SUPPORT

In line with our commitment in providing our customers the highest level of support we will give the following value-added maintenance services that would complement our networking and cabling solution.

1. Provide customer support on the installed cabling system for One (1) year from date of purchase. This is on top of the standard warranty for all products supplied.

2. Additional or changes to the existing system that may be necessarily required which is not covered by the contract shall be arranged and discussed with the customer to be treated as a separate service.

WARRANTY

The following warranty applies:

1. One (1) year workmanship warranty and FREE Maintenance Service
2. Twenty (20) years standard product warranty for cables and components

PAYMENT TERMS AND CONDITIONS

1. Payment- - **Thirty percent (30%) Downpayment**
- **Seventy percent (70%) Progress Billing**

2. Price Validity - Thirty (30) Days from the Quotation Date

3. Availability - On stock items: Three (3) business days.
Special order items: 30 to 45 days upon receipt of confirmed purchase order.

4. Cancellation - There will be Thirty Percent (30%) payment upon the cancellation of Purchase Order.

5. Other Consideration - Any other works and supply not specified in this proposal will be discussed and billed separately.

Thank you very much.

Sincerely yours,

Jayson R. Marasigan
Sales Director
SERG Technologies Inc.
Harrison Mansion F.B. Harrison Pasay City
Mobile: 09566090260
Email: sales@serg-technologies.com
Email: sergtechnologiesinc@gmail.com

Conforme:

Signature over Printed Name