DEZERTECH ENGINEERING & GENERAL MERCHANDISE

General Building, General Engineering, Electrical Works, Mechanical Works
Electromechanical Works, Airconditioning & Refrigeration, Ducting & Fabrication Works,
Communication Facilities, Fire Protection & FDAS Works, Elevator & Escalator Works, Road & Reblocking Works,
Land Development & Heavy Equipment Rentals, Commerce / Trading of Construction & Industrial Supplies,
Engineering Consultancy, Plotting & Blue Printing Services
PCAB LICENSE- GENERAL CONTRACTOR- DESIGN & CONSTRUCT
Office: Central Compound, Crossing, Calamba City
Office Yard: Lot 5, Blk 7, Lakeview, Rosal St. Chipeco Ave. Extn., Halang, Calamba City
Tel No. (049) 530-7461, Mobile No. 0922-890-5824
Email: dezertech_ega@yahoo.com

QUOTATION

QUOTATION No. 07112022 - 4

Customer: PRICON MICROELECTRONICS, INC.
Address: #14 Ampere St. SEPZ, LISP1, Bo. Diezmo, Cabuyao City

Date Prepared: July 11, 2022
Validity : 30days

Attention: Sir Joel C. Padullo
Vice-President for Operations

Thru: Sir Edison Valencia
Sir Nolasco Mendoza
Grinding Area Department

ITEM	QUANTITY	PARTICULARS	UNIT COST	SUB TOTAL
1	1 LOT	SUPPLY OF LABOR & MATERIALS FOR THE ELECTRICAL AND MECHANICAL WORKS DUE TO CNC MACHINES RELOCATION ACTIVITIES (GRINDING AREA) *ELECTRICAL AND MECHANICAL WORKS* *(see attached BOM)* **********NF**********	₱ 92,664.21	₱ 92,664.21
			TOTAL PRICE	₱ 92,664.21

TERMS AND CONDITIONS:

- *Payment 50% down payment & 50% upon completion.*
- *Project completion as per arrangement schedule.*
- *Additional works other than the stated list of scope of works shall be implemented only upon written authorization and shall be subject to a separate quotation and Purchase Order.*
- *Exclusive of temporary space for material storage, power & water supply during the entire construction.*

PROJECT COST ₱ 92,664.21
VAT ZERO-RATED

Prepared by:	Noted by:	Approved by:
djsa	asa	Edezer G. Arias, AMO, GM

email copy only signed original copy is to be hand-carried

Conforme:

Signature Over Printed Name

Thank you for giving us the chance to quote the above item/s as per your deemed request. For any clarification, please send your queries to dezer_tech@yahoo.com.ph or please call (049) 545-6522. We will be glad to hear from you.

BILL OF MATERIALS

PROJECT TITLE: SUPPLY OF LABOR & MATERIALS FOR THE ELECTRICAL AND MECHANICAL WORKS DUE TO CNC MACHINES RELOCATION ACTIVITIES (GRINDING AREA)

CONSTRUCTION DETAILS: ELECTRICAL AND MECHANICAL WORKS

ITEM	SCOPE & MATERIALS	QTY	UNIT	MATERIALS		LABOR		TOTAL			
				UNIT COST	AMOUNT	UNIT COST	AMOUNT	UNIT COST	AMOUNT		
I.	**ELECTRICAL WORKS (RELOCATION OF POWER SUPPLY DROPS FOR CNC MACHINES)**										
	A. FEEDER LINES										
1	22 mm2 THHN	0.1	box	₱ 41,580.00	₱ 4,158.00	₱ 16,632.00	₱ 1,663.20	₱ 58,212.00	₱ 5,821.20		
2	14 mm2 THHN	0.25	box	₱ 27,750.00	₱ 6,937.50	₱ 11,100.00	₱ 2,775.00	₱ 38,850.00	₱ 9,712.50		
3	8.0 mm2 THHN	0.5	box	₱ 14,160.00	₱ 7,080.00	₱ 5,664.00	₱ 2,832.00	₱ 19,824.00	₱ 9,912.00		
4	5.5 mm2 THHN	0.5	box	₱ 8,995.00	₱ 4,497.50	₱ 3,598.00	₱ 1,799.00	₱ 12,593.00	₱ 6,296.50		
5	3.5 mm2 THHN	1	box	₱ 5,500.00	₱ 5,500.00	₱ 2,200.00	₱ 2,200.00	₱ 7,700.00	₱ 7,700.00		
6	Consumables	1	lot	₱ 2,000.00	₱ 2,000.00	₱ 800.00	₱ 800.00	₱ 2,800.00	₱ 2,800.00		
										₱	42,242.20
	B. CONDUIT, CONNECTORS/FITTINGS, ACCESSORIES AND SUPPORT										
1	Ø 40 mm EMT	1	len	₱ 1,107.10	₱ 1,107.10	₱ 442.84	₱ 442.84	₱ 1,549.94	₱ 1,549.94		
2	Ø 32 mm EMT	3	len	₱ 1,038.19	₱ 3,114.56	₱ 415.28	₱ 1,245.83	₱ 1,453.46	₱ 4,360.39		
3	Ø 25 mm EMT	3	len	₱ 647.73	₱ 1,943.18	₱ 259.09	₱ 777.27	₱ 906.82	₱ 2,720.45		
4	Fittings	1	lot	₱ 1,750.00	₱ 1,750.00	₱ 700.00	₱ 700.00	₱ 2,450.00	₱ 2,450.00		
5	Brackets and Support	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00		
6	6" X 6" Pull Box	7	ass'y	₱ 750.00	₱ 5,250.00	₱ 300.00	₱ 2,100.00	₱ 1,050.00	₱ 7,350.00		
7	22 mm2 THHN Butt Connectors	3	pcs	₱ 35.00	₱ 105.00	₱ 14.00	₱ 42.00	₱ 49.00	₱ 147.00		
8	14 mm2 THHN Butt Connectors	9	pcs	₱ 30.00	₱ 270.00	₱ 12.00	₱ 108.00	₱ 42.00	₱ 378.00		
9	8.0 mm2 THHN Butt Connectors	3	pcs	₱ 25.00	₱ 75.00	₱ 10.00	₱ 30.00	₱ 35.00	₱ 105.00		
10	5.5 mm2 THHN Butt Connectors	7	pcs	₱ 20.00	₱ 140.00	₱ 8.00	₱ 56.00	₱ 28.00	₱ 196.00		
11	3.5 mm2 THHN Butt Connectors	6	pcs	₱ 20.00	₱ 120.00	₱ 8.00	₱ 48.00	₱ 28.00	₱ 168.00		
12	Rubber Tape	15	rolls	₱ 120.00	₱ 1,800.00	₱ 48.00	₱ 720.00	₱ 168.00	₱ 2,520.00		
13	Electrical Tape	20	rolls	₱ 50.00	₱ 1,000.00	₱ 20.00	₱ 400.00	₱ 70.00	₱ 1,400.00		
14	Junction Box	15	pcs	₱ 45.00	₱ 675.00	₱ 18.00	₱ 270.00	₱ 63.00	₱ 945.00		
15	Consumables	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00		
										₱	28,489.77
II.	**MECHANICAL WORKS**										
	A. COMPRESSED DRY AIR (Relocation of Airline Drops)										
1	Relocation of Airline Drops	7.00	drop			₱ 950.00	₱ 6,650.00	₱ 950.00	₱ 6,650.00		
2	Ø 15 mm G.I. Pipe	3.00	len	₱ 750.00	₱ 2,250.00	₱ 300.00	₱ 900.00	₱ 1,050.00	₱ 3,150.00		
3	Ø 15 mm G.I. Elbow	14.00	pcs	₱ 95.00	₱ 1,330.00	₱ 38.00	₱ 532.00	₱ 133.00	₱ 1,862.00		
4	Ø 15 mm G.I. Coupling	14.00	pcs	₱ 95.00	₱ 1,330.00	₱ 38.00	₱ 532.00	₱ 133.00	₱ 1,862.00		
5	Ø 15 mm G.I. Nipple	7.00	pcs	₱ 150.00	₱ 1,050.00	₱ 60.00	₱ 420.00	₱ 210.00	₱ 1,470.00		
6	Ø 15 mm G.I. End Cap	7.00	pcs	₱ 75.00	₱ 525.00	₱ 30.00	₱ 210.00	₱ 105.00	₱ 735.00		
7	Hanger, Brackets and Support	1.00	lot	₱ 2,000.00	₱ 2,000.00	₱ 800.00	₱ 800.00	₱ 2,800.00	₱ 2,800.00		
3	CONSUMABLES	1.00	lot	₱ 1,000.00	₱ 1,000.00	₱ 400.00	₱ 400.00	₱ 1,400.00	₱ 1,400.00		
										₱	19,929.00

A.	**GRAND TOTAL OF ITEMS I AND II**		Php	90,660.97
B..	**GENERAL REQUIREMENTS**			
	a. Mobilization / Demobilization		Php	2,000.00
	b. Temporary facilities		Php	-
	c. Site expenses		Php	-
	d. Safety Requirements		Php	-
C.	**INDIRECT COST (Overhead, Supervision)**		Php	-
D.	**CONTRACTOR'S PROFIT**		Php	-
E.	**SUB TOTAL**		Php	92,664.21
F.	***VAT***	*0%*	*Php*	-
	ESTIMATED COST OF PROJECT		**Php**	**92,664.21**
	MODE OF PAYMENT			
	Down Payment	*50%*		
	Upon Completion	*50%*		

Engr. Alvin M. Mancilla
Operations Manager
DEZERTECH ENGINEERING & GEN. MDSE
PCAB-LICENSED CONTRACTOR

Edezer G. Arias
General Manager /AMO
DEZERTECH ENGINEERING & GEN. MDSE
PCAB-LICENSED CONTRACTOR
DESIGN & CONSTRUCT
General Building, General Engineering, Electrical Works,
Mechanical Works, Communication Facilities, Fire Protection & FDAS Works
Elevator & Escalator, Electro Mechanical Works, Airconditioning & Refrigeration,
& Heavy Equipment Rentals, Road, Highway, Pavement, Railway, Airport Horizontal Structure,
Bridges, Irigation and Flood Control, Water Supply, Building & Industrial
Plant, Sewerage and Sewage Treatment / Disposal Plant, Water Treatment Plant
and System, Park, Play Ground and Recreation Work, Land Development, Heavy Equipment Rentals
Commerce & Trading of Construction & Industrial Supplies, Plotting & Blue Printing Services