MANILA OFFICE
Unit 401-402 La Fuerza Plaza I
2241 Don Chinc Roces Ave.,
Makati City 1231
Tel. Nos. +63.2.815.8246 / 47
+63.2.813.0391 / 92
Fax Nos +63.2.840.4939
+63.2.815.8248

MARUKA ENTERPRISES, INC.

To: ***Pricon Microelectronics, Inc.***
14 Ampere St. SEPZ LISP 1
Bo. Diezmo Cabuyao, Laguna
Tel. No. +63.2.843.0870

Attn: **Mr. Watanabe**
Mr. Imano

QUOTATION No.: **QSO20-1969**

Date Quoted: August 5, 2020

Page No.: 1 Of 1

Currency: **Philippine PESO**

Item No.	Description	Qty	Unit Price	Total Amount
	Power Supply Installation for New Stamping Machine			
1	Service Charge	1 lot	1,250,000	1,250,000
	Note: **The following are not included:** Items NOT mentioned, please refer to 2nd Page Permits, Fees and Plans 12% VAT Water and Electricity during construction			
			Total Amount PhP	**1,250,000**

Schedule " to be schedule after receiving of PO and Down Payment
Validitiy: Prices are subject to change without prior notice
Terms of Payment: net 50% Down Payment
net 50% Progress Billing

Noted by:

Mr. Masaki Yoshida
President

MC-EST#S200068

Unique Solutions

MANILA OFFICE
Unit 401-402 La Fuerza Plaza I
2241 Don Chino Roces Ave.,
Makati City 1231
Tel. No:
Fax No:

MARUKA

ITEM	DESCRIPTION	QTY.	UNIT
A	**ELECTRICAL WORKS**		
	POWER SUPPLY FOR MACHINE		
	Model : H1F60-1 - 2 Units		
	18 KVA, 200 Volts, 3-Phase.		
	SMALL POWER SUPPLY FOR CUBICLE BOX		
1.0	**Circuit Breaker To Install @ PP-PROD-5 Panel**		
	75AT/160 AF, 3P, MCCB	2	ea
	20AT/50 AF, 3P, MCCB	2	ea
2.0	**Wires/Cable**		
	22 mm² THHN/THWN	420	lm
	8.0 mm² THHN/THWN	140	lm
	3.5mm²-4C Royal Cord	140	lm
	Wiring accessories	1	lot
	Terminal lugs, rubber cup, vynil tape, cable ties		
3.0	**Wireway/Conduit Piping**		
	150mm W x 2400mm L x 75mmH Solid Bottom	3	lgts
	150mm x 2400mmL Cover	3	lgts
	150mm W x 2400mm L x 100mmH Ladder Straight	6	lgts
	32mmØ x 3000mmL IMC	8	lgts
	32mmØ x 90° IMC elbow	2	ea
	32mmØ Liquidtight Flexible Conduit	10	lm
	25mmØ x 3000mmL IMC	8	lgts
	25mmØ x 90° IMC elbow	2	ea
	25mmØ x 1000mmL Flex. L.T.	10	lm
	Conduit fittings, Connectors	1	lot
	Coupling, Locknut, Bushing, end bells		
4.0	**Supports & Painting materials**	1	lot
	Angle bars, round bars, u-bolts, anchoring matls.		
	Welding & cutting materials, epoxy enamel paint		
B	**Compress Air Piping Works**		
	Modification of existing drop by installation of		
	15 mm Ø Air Coupler, and consummables	2	set
C	**PEZA REQUIREMENTS FOR PERMIT TO INSTALL AND PERMIT T**		
1.0	**Electrical Drawings**	1	lot
	Auto CADD Works & Plotting	5	shts
	Blue Prints A1 Size with Sign & Seal By Professionals	40	shts
	White Prints A3 Size with Sign & Seal By Professionals	20	shts
	PEZA Forms, Sign & Seal By Professionals	1	lot
	Short Circuit Analysis & Voltage Drop Computation	1	lot
2.0	**Mechanical Drawings**	1	lot
	Auto CADD Works & Plotting	5	shts
	Blue Prints A1 Size with Sign & Seal By Professionals	40	shts
	White Prints A3 Size with Sign & Seal By Professionals	20	shts
	PEZA Forms, Sign & Seal By Professionals	1	lot
3.0	**DOLE-CSHP Processing /Safety Requirements**	1	lot