MANILA OFFICE:
UNIT 401 & 402 LA FUERZA PLAZA I,
2241 DON CHINO ROCES AVE.
MAKATI CITY 1231
TEL. NOS. +63.2.8815.8246 to 48
+63.2.8812.0391 & 92
+63.2.8840.4939

MARUKA ENTERPRISES, INC.

To: ***Pricon Microelectronics, Inc.***
14 Ampere St. SEPZ LISP 1
Bo. Diezmo Cabuyao, Laguna
Tel. No. +63.2.843.0870

Attn: **Mr. Watanabe**
Mr. Imano

QUOTATION No.: **QSO21-2075R**

Date Quoted: August 11, 2021

Page No.: 1 0f 1

Currency: **Philippine PESO**

Item No.	Description	Qty	Unit Price	Total Amount
	Power Supply Installation for New Stamping Machine			
1	Service Charge	1 lot	1,100,000	1,100,000
1.1	Less Discount	1 set	(50,000)	(50,000)
	Note: **The following are not included:** Items NOT mentioned, please refer to 2nd Page Permits, Fees and Plans 12% VAT Water and Electricity during construction			
			Total Amount **PhP**	**1,050,000**

Schedule " to be schedule after receiving of PO and Down Payment
Validitiy: Prices are subject to change without prior notice
Terms of Payment: net 50% Down Payment
net 50% Progress Billing

Noted by:

Mr. Masaki Yoshida
President

MC-EST#S2100138

Unique Solutions

MANILA OFFICE:
UNIT 401 & 402 LA FUERZA PLAZA I,
2241 DON CHINO ROCES AVE.
MAKATI CITY 1231
TEL. NOS. +63.2.8815.8246 to 48
+63.2.8812.0391 & 92
+63.2.8840.4939

MARUKA ENTERPRISES, INC.

ITEM	DESCRIPTION	QTY.	UNIT
A	**GENERAL REQUIREMENTS/MOBILIZATION**		
1.0	**Workers Swab Test, PPES, & Temporary Facilities**	1	lot
B	**ELECTRICAL WORKS**		
	POWER SUPPLY FOR MACHINE 1- UNIT PRESS MACH.		
1.0	**Circuit Breaker To Install @ Existing Panel**		
	175AT/250 AF, 3P, MCCB	1	ea
2.0	**Wires/Cable**		
	60 mm² THHN/THWN	225	lm
	14 mm² THHN/THWN	75	lm
	3.5mm²-4C Royal Cord	80	lm
	Wiring accessories	1	lot
	Terminal lugs, rubber cup, vynil tape, cable ties		
3.0	**Cable Tray Obove Ceiling /Conduit Piping**		
	50mmØ x 3000mmL IMC	5	lgts
	50mmØ x 90° IMC elbow	1	ea
	50mmØ x 1000mmL Flex. L.T.	7	lm
	25mmØ x 3000mmL IMC	5	lgts
	Conduit fittings, Connectors	1	lot
	Coupling, Locknut, Bushing, end bells		
4.0	**Supports & Painting materials**	1	lot
	Angle bars, round bars, u-bolts, anchoring matls.		
	Welding & cutting materials, epoxy enamel paint		
C	**Compress Air Piping Works**	1	lot
	Modification of existing drop by installation of		
	15 mm Ø Air Coupler, and consummables		
D	**PEZA REQUIREMENTS FOR PERMIT TO INSTALL AND PERMIT T**		
1.0	**Electrical Drawings**	1	lot
	Auto CADD Works & Plotting	5	shts
	Blue Prints A1 Size with Sign & Seal By Professionals	40	shts
	White Prints A3 Size with Sign & Seal By Professionals	20	shts
	PEZA Forms, Sign & Seal By Professionals	1	lot
	Short Circuit Analysis & Voltage Drop Computation	1	lot
2.0	**Mechanical Drawings**	1	lot
	Auto CADD Works & Plotting	5	shts
	Blue Prints A1 Size with Sign & Seal By Professionals	40	shts
	White Prints A3 Size with Sign & Seal By Professionals	20	shts
	PEZA Forms, Sign & Seal By Professionals	1	lot
3.0	**DOLE-CSHP Processing /Safety Requirements**	1	lot
	Notes:		
	PEZA Submission - by Owner and Magnifico		
	PEZA Assessment Fees - by Owner		
	BFP's FSEC (Fire Safety Evaluation Clearance) /FSIC (Fire Safety Ins		