DEZERTECH ENGINEERING & GENERAL MERCHANDISE

General Building, General Engineering, Electrical Works, Mechanical Works
Electromechanical Works, Airconditioning & Refrigeration, Ducting & Fabrication Works,
Communication Facilities, Fire Protection & FDAS Works, Elevator & Escalator Works, Road & Reblocking Works,
Land Development & Heavy Equipment Rentals, Commerce / Trading of Construction & Industrial Supplies,
Engineering Consultancy, Plotting & Blue Printing Services
PCAB LICENSE- GENERAL CONTRACTOR- DESIGN & CONSTRUCT
Office: Central Compound, Crossing, Calamba City
Office Yard: Lot 5, Blk 7, Lakeview, Rosal St. Chipeco Ave. Extn., Halang, Calamba City
Tel No. (049) 530-7461, Mobile No. 0922-890-5824
Email: dezertech_ega@yahoo.com

QUOTATION

QUOTATION No. 09232022 - 4
REV.EGA.09282022-01

Customer: PRICON MICROELECTRONICS, INC.
Address: #14 Ampere St. SEPZ, LISP1, Bo. Diezmo, Cabuyao City

Date Prepared: September 23, 2022
Validity : 30days

Attention: Sir Joel C. Padullo
Vice-President for Operations

Thru: Sir Edison Valencia
Sir Olan Nolasco
Grinding Area Department

ITEM	QUANTITY	PARTICULARS	UNIT COST	SUB TOTAL
1	1 LOT	SUPPLY OF LABOR & MATERIALS FOR TWO (2) ADDITIONAL ROBODRILL MACHINES (GRINDING AREA) ***ELECTRICAL WORKS*** **(see attached BOM)** **********NF**********	₱ 145,918.99	₱ 145,918.99
			TOTAL PRICE	₱ 145,918.99

TERMS AND CONDITIONS:

- ***Payment 50% down payment & 50% upon completion.***
- ***Project completion as per arrangement schedule.***
- ***Additional works other than the stated list of scope of works shall be implemented only upon written authorization and shall be subject to a separate quotation and Purchase Order.***
- ***Exclusive of temporary space for material storage, power & water supply during the entire construction.***

PROJECT COST ₱ 145,918.99
VAT ZERO-RATED

Prepared by:	Noted by:	Approved by:
djsa	asa	Edezer G. Arias, AMO, GM

email copy only signed original copy is to be hand-carried

Conforme:

Signature Over Printed Name

Thank you for giving us the chance to quote the above item/s as per your deemed request. For any clarification, please send your queries to dezer_tech@yahoo.com.ph or please call (049) 545-6522. We will be glad to hear from you.

BILL OF MATERIALS

PROJECT TITLE: SUPPLY OF LABOR & MATERIALS FOR TWO (2) ADDITIONAL ROBODRILL MACHINES (GRINDING AREA)

CONSTRUCTION DETAILS: ELECTRICAL WORKS

ITEM	SCOPE & MATERIALS	QTY	UNIT	MATERIALS		LABOR		TOTAL		
				UNIT COST	AMOUNT	UNIT COST	AMOUNT	UNIT COST	AMOUNT	
I.	**ELECTRICAL WORKS**									
	A. CIRCUIT BREAKERS									
	1 40 AT CIRCUIT BREAKER, 3P	2	sets	₱ 9,643.21	₱ 19,286.42	₱ 3,857.28	₱ 7,714.57	₱ 13,500.50	₱ 27,000.99	
	2 BUS BAR SET FOR 40 AT CIRCUIT BREAKERS, 3P	1	set	₱ 7,500.00	₱ 7,500.00	₱ 3,000.00	₱ 3,000.00	₱ 10,500.00	₱ 10,500.00	
	3 CONSUMABLES	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
										₱ 39,600.99
	B. FEEDER LINES									
	1 8.0 mm2 THHN	2	box	₱ 8,280.00	₱ 16,560.00	₱ 3,312.00	₱ 6,624.00	₱ 11,592.00	₱ 23,184.00	
	2 5.5 mm2 THHN	1	box	₱ 7,579.00	₱ 7,579.00	₱ 3,031.60	₱ 3,031.60	₱ 10,610.60	₱ 10,610.60	
	3 8.0 - 8.0 TERMINAL LUGS	12	pcs	₱ 75.00	₱ 900.00	₱ 30.00	₱ 360.00	₱ 105.00	₱ 1,260.00	
	4 5.5 - 5.5 TERMINAL LUGS	4	pcs	₱ 50.00	₱ 200.00	₱ 20.00	₱ 80.00	₱ 70.00	₱ 280.00	
	5 CONSUMABLES	1	lot	₱ 2,000.00	₱ 2,000.00	₱ 800.00	₱ 800.00	₱ 2,800.00	₱ 2,800.00	
										₱ 38,134.60
	C. CONDUIT, CONNECTORS/FITTINGS, ACCESSORIES AND SUPPORT									
	1 Ø 25 mm EMT	8	len	₱ 647.73	₱ 5,181.80	₱ 259.09	₱ 2,072.72	₱ 906.82	₱ 7,254.52	
	2 Fittings	1	lot	₱ 2,500.00	₱ 2,500.00	₱ 1,000.00	₱ 1,000.00	₱ 3,500.00	₱ 3,500.00	
	3 Brackets and Support	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
	4 Ø 25 mm LQT	10	m	₱ 400.00	₱ 4,000.00	₱ 160.00	₱ 1,600.00	₱ 560.00	₱ 5,600.00	
	5 Ø 25 mm LQT Adapter	4	pcs	₱ 200.00	₱ 800.00	₱ 80.00	₱ 320.00	₱ 280.00	₱ 1,120.00	
	6 Rubber Tape	5	rolls	₱ 120.00	₱ 600.00	₱ 48.00	₱ 240.00	₱ 168.00	₱ 840.00	
	7 Electrical Tape	10	rolls	₱ 50.00	₱ 500.00	₱ 20.00	₱ 200.00	₱ 70.00	₱ 700.00	
	8 Junction Box	10	pcs	₱ 45.00	₱ 450.00	₱ 18.00	₱ 180.00	₱ 63.00	₱ 630.00	
	9 Ø 25 mm U-Bolt with nuts	4	pcs	₱ 48.00	₱ 192.00	₱ 19.20	₱ 76.80	₱ 67.20	₱ 268.80	
	10 Orange Paint	9.05	sq.m.	₱ 350.00	₱ 3,166.73	₱ 140.00	₱ 1,266.69	₱ 490.00	₱ 4,433.43	
	11 Consumables	1	lot	₱ 1,500.00	₱ 1,500.00	₱ 600.00	₱ 600.00	₱ 2,100.00	₱ 2,100.00	
										₱ 28,546.75

A.	**GRAND TOTAL OF ITEMS I AND II**		Php	106,282.34
B..	**GENERAL REQUIREMENTS**			
	a. Mobilization / Demobilization		Php	5,000.00
	b. Temporary facilities		Php	-
	c. Site expenses		Php	2,500.00
	d. Safety Requirements		Php	2,500.00
C.	**INDIRECT COST (Overhead, Supervision)**		Php	5,314.12
D.	**CONTRACTOR'S PROFIT**		Php	24,319.29
E.	**SUB TOTAL**		Php	145,918.99
F.	***VAT***	*0%*	*Php*	-
	ESTIMATED COST OF PROJECT		**Php**	**145,918.99**
	MODE OF PAYMENT			
	Down Payment	*50%*		
	Upon Completion	*50%*		

Engr. Alvin M. Mancilla
Operations Manager
DEZERTECH ENGINEERING & GEN. MDSE
PCAB-LICENSED CONTRACTOR

Edezer G. Arias
General Manager /AMO
DEZERTECH ENGINEERING & GEN. MDSE
PCAB-LICENSED CONTRACTOR
DESIGN & CONSTRUCT
General Building, General Engineering, Electrical Works, Sanitary & Plumbing Works
Mechanical Works, Communication Facilities, Fire Protection & FDAS Works
Elevator & Escalator, Electro Mechanical Works, Airconditioning & Refrigeration,
& Heavy Equipment Rentals, Road, Highway, Pavement, Railway, Airport Horizontal Structure,
Bridges, Irigation and Flood Control, Water Supply, Building & Industrial
Plant, Sewerage and Sewage Treatment / Disposal Plant, Water Treatment Plant
and System, Park, Play Ground and Recreation Work, Land Development, Heavy Equipment Rentals
Commerce & Trading of Construction & Industrial Supplies, Plotting & Blue Printing Services