ENGAUGE HYDRAULICS CORP.
L33, B37, 2nd Greenstone St.,
Green Valley Subdivision, Molino,
Bacoor, Cavite, 4102 Philippines
Tel : +632-87104981
Fax :
Email : engaugehyd@yahoo.com

REF:
DATE 16-Dec-2021
FAX NO.
TEL. NO.
EMAIL rebvale@pricon.ph

Costumer : **Pricon Microelectronics, Inc.**
Address : LISP1, Cabuyao, Laguna
Attention : Ms. Rebecca D. Valenzuela

QUOTATION

Item	Description / Part No.	Qty	U/M	Unit Price	Amount
1	Complete resealing of hydraulic power pack components	1	Lot	55,000.00	55,000.00
	for Sodick injection machine TR55EH2 #18 except main				
	pump with the following scope of works.				
	1. Machine function/performane test.				
	2. Machine Shut Down.				
	3. Drain power pack of hydraulic oil.				
	4. Disassemble individual hydraulic power pack components				
	including clamp valve stack assembly.				
	5. Inspect, clean, and overhaul individual components.				
	6. Complete resealing of individual components.				
	7. Dismantle all manifold hose adaptors for resealing.				
	8. Installation and machine testing.				
	Note:				
	1. Parts found defective after disassembly will be quoted				
	separately for repair or replacement.				
	2. Price quoted includes the standard sealing materials.				
	3. PMI will provide the oil transfer cart and empty				
	container for draining of hydraulic oil.				
	4. Hydraulic power pack pump and oil cooler disassembly				
	for cleaning not included.				
	5. Electrical works and accessories not included.				
	6. Hydraulic oil is not included.				

TERMS AND CONDITIONS

Delivery : 1 day upon receipt of firm order.		55,000.00
Payment : 30 days		
Validity : 30 days		
Prepared By : Ver Casas		**Final Amount PHP**
Sales Engineer	Conforme	VAT Excluded